

## Vienna Airport Terminal 2, Baggage Reclaim Hall South and Redesign of Plaza

**Client:**

Flughafen Wien AG

**Country:**

Austria

**Duration:**

From 24.09.2018 to 31.05.2021

**Services:**

Site supervision  
Construction coordination

**Project objectives**

New uses should be given to the currently unused areas in Terminal 2 and the adjacent objects. A partial security control and a baggage reclaim hall are being built.

The building substance is being refurbished and the building services updated and adapted. In addition to this, a lounge is being built.

**Project description**

- Construction of a new roof in place of the suspended roof structure, including all necessary structural adaptation and reinforcement work
- New construction and adaptation of the building services
- Adaptation of the fire protection in line with the latest technical standards and the new functions, construction of new escape stairs and escape routes
- Addition of a security control and the associated boarding card control
- Construction of retail and waiting areas
- Creation of generous lounges
- Construction of areas for security and border controls
- Construction of baggage claim area with three baggage carousels and airside connection
- Adaptation of the plaza (central shopping area)
- Adaptation of the signage and the shop layout

**Project data**

Construction costs are approximately EUR 51 million. The construction period stretches from November 2018 to March 2021.

**Project specifics**

The measures are being realised in a number of phases without interrupting normal operations.

**Services**

Site supervision including specialist site supervision in the areas of electrical engineering, ICT, HVAC and MCR as well as site coordination in line with the Construction Work Coordination Act (BauKG).

